BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 Indent No.20431

SCHEDULE-B

NAME OF WORK: Construction of RCC drain in6th cross road at prashantha nagara in ward no.13, Shetty halli sub division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor M S MURULIDHARA		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specfication & as per direction of Engineer-in-charge	Cum	99.9	83.16	Rupees Eighty Three and Sixteen Paise Only	8307.68
2	Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specfication & as per direction of Engineer-in-charge	Cum	19.98	5139.94	Rupees Five Thousand One Hundred Thirty Nine and Ninety Four Paise Only	102696.00
3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed -2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings,pedastals,retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specfication & as per direction of Engineer-in-charge	Cum	61.95	6083.34	Rupees Six Thousand Eighty Three and Thirty Four Paise Only	376862.91

gnature of the Contractor

Executive Engineer

4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specfication & as per direction of Engineer-in-charge	Qtl	37.17	5358.0	Rupees Five Thousand Three Hundred Fifty Eight Only	199156.86
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walss at any thickness,including attached pilasters,buttresses, plinth and string courses cost of all materials, labour complete as per specfication & as per direction of Engineer-in-charge	Sqm	314.8	301.04	Rupees Three Hundred One and Four Paise Only	94767.39
6	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & complete as per specfication & as per direction of Engineer-in-charge	Sqm	10.8	1600.0	Rupees One Thousand Six Hundred Only	17280.00
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specfication & as per direction of Engineer-in-charge	Cum	90	81.73	Rupees Eighty One and Seventy Three Paise Only	7355.70
					Total	806426.55
					Percentage	-6.44%

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

gnature of the Contractor

Executive Engineer